









#### LIGHT HOUSE PROJECT: LIVE LABORATORIES

#### WEBINAR SERIES: e-learning & webcasting of LHPs for TECHNOGRAHIS March – November 2022

An 'e-Learning series and webcasting of LHP's construction process' to widespread the knowledge about the technology, construction process, sustainability, and mass cum fast construction to TECHNOGRAHIs.

## Webinar Session #07 at Light House Project Rajkot, Gujarat

Date: 04.05.2022, Wednesday | Time: 16:00 – 17:30



















Light House Projects : Live Laboratories Webinar Series

# Emerging Construction Systems for Mass Housing





#### PMAY (U) Achievement (provisional)

[as on 2nd May, 2022]



#### Overall Sanctions for 1.23 crore Houses



Demand 112.24

#### Construction of Houses (Nos in lakh)

Sanctioned

Grounded 122.69 98.36

ampleted Detven

58.68



Committed 203,427

#### Financial Progress (₹ in Cr)

Released 118,020

Expenditure 110,481

UC Received 109,974



#### Houses in verticals (Nos in Lakh)

5- Sanctioned C- Completed G-Grounded Pet to Release 23.97 lakh

Beneficiaries under CLSS (in lakh)



Investment Approved (Rs in Lakh Cr.)



Interest Subsidy under CLSS (Rs in Cr.)



#### PMAY (U) Achievement (provisional)

[as on 2nd May, 2022]



#### 16 lakh houses are being constructed using New Technologies



#### Details

Person days (Nos in Cr.)

Jobs (in lakh)

#### Generation of Employment

Direct 212

76

Indirect

474


169

Total

686

245





<sup>\*</sup> includes incomplete works of earlier NURM.





#### https://ghtc-india.gov.in/


CHALLENGE INDIA



Categories	Technology	Tech. Providers
1	Precast Concrete Construction System - 3D Precast volumetric	4
2	Precast Concrete Construction System - Precast components assembled at site	8
3	Light Gauge Steel Structural System & Pre-engineered Steel Structural System	16
4	Prefabricated Sandwich Panel System	9
5	Monolithic Concrete Construction	9
6	Stay In Place Formwork System	8
	Total	54





















## Light House Projects



Hon'ble Prime Minister laid the foundation stone of six LHPs on 01.01.2021



#### **Conventional Construction Systems**

business as usual approach

The prevalent construction systems in India are: Load bearing Structure

In this system, walls are constructed using bricks/stone/block masonry and floor/roof slabs are of RCC/stone/composite or truss. It is cast insitu system and called load bearing system as load of structure is transferred to foundation and then to ground through walls.



#### **RCC Framed Structure**

In this cast in-situ system, the skeleton of a structure is of RCC column and beam with RCC slab. The infill walls can be of bricks/blocks/stone /panels. The load of the structure is transferred through beam and column to the foundation.





#### **Conventional Construction Systems**

#### **Alternate Construction Systems**

Slow

Maximum Use of Natural Resources

**Waste Generation** 

Air/Land/Water Pollution

**Labour Intensive** 

**Prescriptive Design** 

**Unhealthy Indoor Quality** 

Regular Maintenance

**Energy Intensive** 

Cast-in-situ Poor Quality

**High GHG Emissions** 

Unsustainable

**Fast** 

**Optimum use of Resources** 

**Minimum Waste** 

**Minimum Pollution** 

**Industrialized System** 

**Cost-effective Design** 

**Better health & Productivity** 

Low Life Cycle Cost

**Energy Efficient** 

**Factory Made Quality Products** 

**Low GHG Emissions** 

Sustainable



#### Emerging construction systems help to build

### SAFER structures

#### **Sustainable Buildings**

- ❖ 30%-50% reduction in energy use
- ❖ 40% reduction in water use
- **❖** 35% reduction in GHG emission
- ❖ 75% reduction in waste

LCOHOIIICAI - low me cycle cost, better quanty

R

Resilient -

disaster-resistant, structurally superior



#### **3D Precast Volumetric Construction**

- Replacing cast in situ RCC structural frame with factory made structural components – 3D
- Customized factory made volumetric construction i.e. the entire module (room)





#### **3D MONOLITHIC VOLUMETRIC Construction**









**Courtesy:** 



Precast Concrete
Construction System –
3D Volumetric

1	Pre-cast concrete system with columns, beams, walls, slabs, hollow core slabs & also 3D Volumetric components	Katerra
2	Vertical structural modules cast in Plant/Casting yard are assembled together through casting of floor panel. The unit is transported & installed at site.	Moducast Pvt. Ltd
3	3D Modular casting using steel mould and high performance concrete of building modules in factory. These pods are transported to the construction site & assembled	The state of the s
4	Modules with 3D Volumetric Precast concrete unit, various units make on house	Ultratech Cement Ltd,



#### Light House Project (LHP) at Ranchi, Jharkhand

(Technology: Precast Concrete Construction – 3D Volumetric Construction)



#### **2D Precast Concrete Construction**

- Replacing cast in situ RCC structural frame with factory made structural components – 2D planar elements
- Customized Factory made beams, columns, wall panels, slab/floors, staircases etc.





## Concrete components prefabricated in precast yard or site and installed in the building during construction















2

#### Precast Concrete Construction System – Precast components assembled at site

1	Precast Large Concrete Panel (PLCP) System with structural members (wall, slab etc.) cast in a factory/ casting yard and brought to the building site for erection & assembling	
2	Pre-cast Concrete Structural system comprising of pre-cast column, beam, precast concrete / light weight slab, AAC blocks/ infill concrete walls.	
3	Optimal Pre-cast concrete System through structural Analysis, design & equipment support	Elematic India,
4	Precast concrete construction system using precast walls with precast plank floor	PG Setty Construction Technology Pvt Ltd,
5	Precast components comprising of beams, coloumns, staircase, slab, hollow core slab etc. manufactured in plant & erected on site	Teemage
6	Pre-cast sandwich panel system & Light weight Pre cast Light Weight concrete slab	Nordicflex
7	Prefabricated Interlocking Technology (without mortar) with Roofing as Mechnized Precast R.C. Plank & Joist system	Adalakha Associates Pvt. Ltd
8	Large Hollow wall prefab concrete Panel (lightweight, interlocking, concrete panel) using factory produced large standard hollow interlocking concrete block	William Ling,



#### Light House Project (LHP) at Chennai, Tamil Nadu

(Technology: Precast Concrete Construction System-Precast Components)



## PRE-ENGINEERED STEEL STRUCTURAL SYSTEM

Replacing cast in situ RCC structural frame with factory made steel (hot rolled) structural system







Steel skeleton with Aerocon panel infills



## LIGHT GAUGE STEEL STRUCTURAL SYSTEMS

 Replacing cast in situ RCC structural frame

> with factory made light gauge steel (cold rolled) structural system





3

## Light Gauge Steel Structural System & Preengineered Steel Structural System

1	LGS Framing with various walling & roofing options	Mitsumi Housing Pvt. Ltd,
		Process of the description and
2	LGS Framing with various walling & roofing options	Everest Industries Ltd,
3	LGS Framing with various walling & roofing options	JSW Steel Ltd.,
4	LGS Framing with various walling & roofing options	Society for Development of Composites
5	LGS Framing with various walling & roofing options	Elemente Designer Homes
6	LGS Framing with various walling & roofing options	MGI Infra Pvt. Ltd.,
7	LGS Framing with various walling & roofing options	RCM Prefab Pvt. Ltd,
8	LGS Framing with various walling & roofing options	Nipani Infra and
		Industries Pvt. Ltd.,
9	LGS Framing with various walling & roofing options	Strawcture Eco
10	LGS Framing with various walling & roofing actions	Visakha Industries Ltd.
11	Prefabricated steel structural system with Dry wall	RCC Infra Ventures Ltd.
	system as AAC panels, PUF panels etc	
12	Hot rolled steel frame with speed floor	Jindal Steel & Power Ltd.
13	Hot rolled steel section with AAC Panels as floor &	HIL Ltd.
	slab	
14	AAC wall and roof panel system to provide integrated	Biltech Building Elements
	solution. AAC products are reinforced and used in	Ltd
	both load and non-load bearing applications	
15	AAC Panels are Wire mesh/ steel reinforced for use as	SCG International India
	wall & slab. Appears to be non load bearing panels to	Pvt Ltd
	be used with structural framing.	
16	Precast Light Weight Hollow-core wall Panel is a non-	Pioneer Precast Solutions
	structural construction material with framed	Private Limited
	structures.	



#### Light House Project (LHP) at Agartala, Tripura

(Technology: Light Gauge Steel Structural System & Pre-Engineered Steel Structural System)



## PREFABRICATED SANDWICH PANEL SYSTEMS





- EPS Core Panel Systems
- Other Sandwich Panel Systems
  - Fibre cement board
  - MgO Board
  - AAC panels













 Replacing brick and mortar walls with dry customized walls made in factory








SINGLE





DOUBLE









4

#### Prefabricated Sandwich Panel System

1	Reinforced Expanded Polystyrene sheet core Panel with sprayed concrete as wall & slab	Worldhaus
2	EPS Cement sandwich Panel: wall & slab with EPS	•
	Cement sandwich Panel to be used with RCC or	
	Steel structural frame. Load bearing upto G+1 storey	Pvt.Ltd
3	EPS Cement sandwich Panel: wall & slab with EPS	Rising Japan Infra
	Cement sandwich Panel to be used with RCC or	Private Limited
	Steel structural frame. Load bearing upto G+1	
	storey	
4	Reinforced Expanded Polystyrene sheet core	Bau Panel Systems
	Panel with sprayed concrete as wall & slab	India Pvt Ltd,
5	Reinforced Expanded Polystyrene sheet core	BK Chemtech
	Panel with sprayed concrete as wall & slab	Engineering
6	Reinforced Expanded Polystyrene sheet core	MSN Construction
	Panel with sprayed concrete as wall & slab	
7	Reinforced Expanded Polystyrene sheet core	Beardshell Ltd.
	Panel with sprayed concrete as wall & slab	
8	Pre-fab PIR (Poly-isocyanurate) based Dry Wall	Covestro India Pvt.
	Panel System" as non-load bearing wall	Ltd.,
9	Sandwich panels as wall & slab	Project Etopia
		Group



#### Light House Project (LHP) at Indore, M.P.

(Technology: Prefabricated Sandwich Panel System & Pre-Engineered Steel Structural System)



No. of Dwelling Units: 1024 Nos. (S+8)

Units in each Block / Tower: 128 Nos.

#### Rising EPS (Beads) Cement Panels



- Rising EPS (Beads) Cement Panels are patented panels from M/s Rising Japan Infra Pvt. Ltd. These are lightweight composite wall, floor and roof sandwich panels made of thin fiber cement/calcium silicate board as outer and inner faces with a core of EPS granule balls, adhesive, cement, sand, fly ash and other bonding materials in mortar form.
- The core material in slurry state is pushed under pressure into preset molds. Once set, it shall be moved for curing and ready for use with RCC or steel framed structure.
- These panels were manufactured by the firm in China and now two plants at Nagpur & Pune are operational in India.



## MONOLITHIC CONCRETE CONSTRUCTION

- Replacing cast-in-situ
   Formwork with factory
   made customized
   formwork systems
- Formwork material is Aluminium / composites / steel having 100 to 500 repetitions
- Assembly line construction i.e. placing the formwork, pouring the concrete, moving the formwork to upper level










#### **Monolithic Concrete Construction**

1	Aluminium formwork system for Monolithic Concrete construction	Maini Scaffold Systems
2	Aluminium formwork system for	KumkangKind India
	Monolithic Concrete construction	Pvt. Ltd
3	Aluminium formwork system for	S-form India Pvt. Ltd.,
	Monolithic Concrete construction	
4	Aluminium formwork system for Monolithic	ATS Infrastructure Ltd.
	Concrete construction	
5	Aluminium formwork system for Monolithic	Innovative housing &
	Concrete construction	Infrastructure Pvt. Ltd
6	Aluminium formwork system for Monolithic	MFS formwork
	Concrete construction	Systems Pvt. Ltd.
7	Aluminium formwork system for	<b>Knest Manufacturers</b>
	Monolithic Concrete construction	LLP
8	'Tunnel form' construction technology, an cast	Outinord Formworks
	in situ RCC system, based on the use of high-	Pvt. Ltd.
	precision, re- usable, room-sized, steel forms or	
	moulds for monolithic concrete construction	
9		Prilliant Etaila
9	Aluminium formwork system for Monolithic	Diffilialit Etolie
	Concrete construction	



#### Light House Project (LHP) at Rajkot, Gujarat

(Technology: Monolithic Concrete Construction System)



#### **Modular Tunnel form**




- Tunnel formwork is a mechanized system for cellular structures. It is based on two half shells which are placed together to form a room or cell. Several cells make an apartment. With tunnel forms, walls and slab are cast in a single day.
- The formwork is set up for the day's pour in the morning. The reinforcement and services are positioned and concrete is poured in the afternoon. Once reinforcement is placed, concrete for walls and Slabs shall be poured in one single operation. The formwork is stripped the early morning and positioned for the subsequent phase.
- Here the walls and slabs are cast in a form of a tunnel leaving two sides open whereas in monolithic concrete construction the entire room is cast in a single pour..



STAY-IN-PLACE FORMWORK SYSTEM

- Replacing cast-in-situ
  Formwork with factory
  made formwork
  systems
- It is sacrificial formwork or lost formwork means formwork is left in the structural system to later act as insulation or reinforcement cage















## **Global Housing Technology Challenge - India (GHTC-I)**

6

#### Stay In Place Formwork System

1	Expanded-Steel Panel reinforced with all- galvanised Steel Wire-Struts serving both as the load- bearing steel structure and as the stay-in-place steel formwork filled with EPS-alleviated concrete	
2	Factory made prefab Glass fibre reinforced Gypsum cage panels suitable for wall & slab with reinforcement & concrete as infill as per the requirement	<del>-</del>
3	Structural Stay In Place Galvanized Steel formwork system for walling with the same bottom single layer formwork for slabs/in-situ slab	
4	Factory produced PVC Stay in place formwork with concrete & reinforcement in walling units with cast insitu RCC Slab	Joseph Jebastin (Novel Assembler)
5	Fully load bearing walls with 150 mm monolithic concrete core sandwiched inside two layers of EPS as walling The forms are open ended hollow polystyrene interlocking blocks which fits together to form shuttering system	
6	Ready to use Stay in place polymer formwork, light weight, with flooring slab (combination of ferro cement and natural stone) placed on RCC precast joists)	
7	Fast Bloc, Insulated Concrete Form (ICF), acts as formwork for concrete and rebar, Co1oumn/post and beam construction, creating an strong skeleton in the walls.	_
8	Formwork system "Plaswall with Two fibre cement boards (FCB) & HIMI (High Impact Molded Inserts) bonded between two sheets of FCB in situ and erected to produce a straight-to finish wall with in-situ concrete	Pvt.Ltd



## Light House Project (LHP) at Lucknow, U.P.

(Technology: Stay in-place Formwork System & Pre-Engineered Steel Structural System)



## **Stay-In-Place PVC Wall Forms**



- The extruded components slide and interlock together to create continuous formwork with the two faces of the wall connected together by continuous web members forming hollow rectangular components. The web members are punched with oval-shaped cores to allow easy flow of the poured concrete between the components.
- The hollow Novel Wall components are erected and filled with concrete, in situ, to provide a monolithic concrete wall.

This is a prefinished wall formwork from M/s Novel Assembler Pvt. Ltd. comprising of rigid Poly-Vinyl Chloride (PVC) based polymer components that serve as a permanent stay-in-place durable finished form-work for concrete walls.





## **Adoption of New Technologies by States**



AHP houses in Pune, Maharashtra using Precast Construction Technology

 Around 16 Lakh houses are being built using innovative technologies under PMAY(U) & other state schemes.

State	Technology	
Andhra Pradesh	EPS, Monolithic and Steel Technology	
Chhattisgarh	Monolithic and Precast Technology	
Gujarat	Monolithic, Precast (Waffle-crete)	
Kerala	Glass Fibre Reinforced Gypsum (GFRG)	
Maharashtra	Precast (3S) & Monolithic Technology	
Odisha	Precast concrete construction	
Jharkhand	Global Tender floated	
Tamil Nadu	Precast Concrete Technology	
States like Assam, Karnataka, Madhya Pradesh, Telangana &		

Uttarakhand have also expressed interest in Technology

neutral bidding process

Alternate technologies Identified

technologies approved by CPWD


**29**SoRs issued


SoRs issued for alternate technologies by CPWD (22+7)



### Looking Back / Rear view

Levels of Construction Technology







Courtesy : hol









# Light House Project at RAJKOT

**GHTC-I Category:** 

**Monolithic Concrete Construction System** 

**Technology:** 

**Monolithic Concrete Construction using Tunnel Formwork** 




- Have a look at the project brief:
  - 1144 houses will be constructed in Stilt+13 configuration.
  - The total plot area is around 39,600 Sqm and carpet area of each house is approximately 39.77 Sqm.
  - There are 11 residential blocks.
  - The project also includes Community Centre and Health Centre.

#### Typical floor plan



At each floor there are 08 dwelling units





#### Typical Dwelling Unit Plan



**Unit Plan** 

- Each dwelling unit comprises of one living room, one Bedroom, one study room, Kitchen and two toilets.
- The carpet area of each unit is 39.77 sq.mt. The sizes of individual rooms & service areas conform to NBC norms.
- Other special features:
- Green rating as per GRIHA
- Use of renewable resources:
  - Rain water harvesting
  - Solar lighting
- Solid waste management
- STP with recycling of waste water




Unit 3D Vlew



#### **Structural Elements**

## **Assembly of Tunnel Formwork**








#### **Structural Elements**


#### **Work Cycle with Tunnel Formwork**

The on-site implementation of 24 hour cycle is divided into following operations.

- 1. Stripping of the formwork from the previous day.
- 2. Positioning of the formwork for the current day's phase, with the installation of mechanical, electrical and plumbing services.
- Installation of reinforcement in the walls and slabs.
- 4. Concreting.











## **MEP**





In Shear walls, the plumbing and electrical services are incorporated before casting. In AAC Block walls, the plumbing and electrical services are incorporated as done in conventional method of construction i.e. chasing and filling



#### **Structural Elements**

## **Structural System**





Placement of tunnel formwork for slab and wall

• Concreting after placement of reinforcement on slab and wall.



# Present Stage of Work (As on May 02, 2022)

Activities		Progress	
Foundation work	:	Completed in all 11 blocks.	
Superstructure work	:	8 Blocks completed (Block no.1,2,3,4,7,8,9,10 & 11)	
		Block No. 5- Ground +10 work is completed	
		Block No. 6- Ground +7 work is completed	
Sample Unit	:	Completed	
Masonry work	:	Completed – 7 blocks	
		In progress – 4 blocks	
Internal Building work	:	Internal plaster is completed in 6 blocks & in-progress in 4 blocks.	
		Kitchen slab, tile work and plumbing are in progress. Installation of	
		lifts is also in progress.	
Internal (electrical work)	:	In progress – 10 blocks	
Social & Physical	:	After completion of Structure work, the Internal finishing is in progress	
Infrastructure works		in Anganwadi cum Shopping Complex and community centre both.	
		Plaster work both internal and external completed.	
<b>External Infrastructure</b>	•	Infrastructure works including Sewer line, storm water drains, water	
		supply works, boundary wall, fire fighting etc. are in progress.	



# **Towers in Progress Photographs**











Tower 1 Tower 2







Tower 3 Tower 4







Tower 5 Tower 6







Tower 7 Tower 8







Tower 9 Tower 10





**Tower 11** 





Anganwadi cum shopping centre

**Community Centre** 



## Overall Project as on May 04, 2022







You can reach us at <a href="mailto:ska@bmtpc.org">ska@bmtpc.org</a>; <a href="mailto:info@bmtpc.org">info@bmtpc.org</a>;



@bmtpcdelhi



bmtpc.mhua

"Creating Enabling Environment for Affordable Housing for All"

