









MoHUA

'Housing for All' by 2022.

Under the Mission, Ministry of Housing and Urban Affairs (MoHUA), provides Central Assistance to implementing agencies through States and Union Territories for providing houses to all eligible families/beneficiaries by 2022.

Addressing the affordable housing requirement in urban areas through: Affordable Housing in Partnership with Public & Private Sectors

Subsidy for Beneficiary-Led individual house construction/ enhancement. In-situ Slum Redevelopment (ISSR) for Slums

Promotion of Affordable Housing through CLSS

Slum rehabilitation of Slum Dwellers with participation of private developers using land as a resource.

MoHUA







GIZ

- GIZ is an international cooperation enterprise for sustainable development which operates worldwide, on a public benefit basis.
- GIZ is fully owned by the German Federal Government, GIZ implement development programs in partner country on behalf of the German Government in achieving its development policy objectives.





Session on LHPs









Six Light House Projects (LHPs)

1. Ranchi, Jharkhand

• Precast Concrete Construction System – 3D Volumetric

2. Rajkot, Gujarat

Monolithic Concrete Construction using Tunnel Formwork

3. Chennai, Tamil Nadu

Precast Concrete Construction System – Precast Components Assembled at Site

4.Indore, Madhya Pradesh

• Prefabricated Sandwich Panel System

5.Agartala, Tripura

• Light Gauge Steel Structural System & Pre-engineered Steel Structural System

6.Lucknow, Uttar Pradesh

• PVC Stay In Place Formwork System









Summary of Six Light House Projects (LHPs)

LHP Location			Chennai	Rajkot	Indore	Ranchi	Agartala	Lucknow
S1. No	Particulars	Units	(Tamil Nadu)	(Gujarat)	(Madhya Pradesh)	(Jharkhand)	(Tripura)	(Uttar Pradesh)
1	Name of Technology	Name	Precast Concrete Construction System- Precast Components	Monolithic Concrete Constructio n using Tunnel Formwork	Prefabricated Sandwich Panel System	Precast Concrete Construction System – 3D Volumetric	Light Gauge Steel Frame System (LGSF) with Pre- Engineered Steel Structural System	Stay in Place Formwork System
2	No. of Houses	No.	1,152	1,144	1,024	1,008	1,000	1,040
3	No. of Floors	No.	G+5	S+13	S+8	G+8	G+6	S+13
4	Plot Area	Sqm	33,596	39,599	41,920	31,160	24,000	20,000
5	Per House Carpet Area	Sqm	26.58	39.77	29.04	29.85	30.00	34.50
6	Project Cost	INR (in Cr)	116.27	118.90	128.00	134.00	162.50	130.90
7	Per House cost (with infrastructure)	INR (in Lakh)	10.09	10.39	12.50	13.29	16.25	12.58







- There are 7 blocks in Ground + 8 configuration with 1008 houses along with basic and social infrastructure.
- Ground coverage of the project is 29.3% and FAR is 2.21.
- Green space is 20%.



Typical floor plan



16 dwelling units at each floor of building block with provision of lifts and staircases.









Typical Dwelling Unit plan



Each dwelling unit consists of one hall, one bed room, a kitchen, WC, Bath and a balcony. The carpet area of each unit is 29.85 Sq.mt. The sizes of individual rooms & service areas conform to NBC norms.



Other special features:

- Green rating as per GRIHA
- Use of renewable resources:
 - Rain water harvesting
 - Solar lighting
- Solid waste management
- STP with recycling of waste water
- Fire Fighting System conforming to NBC









Conventional Construction Systems

The prevalent construction systems in India are: *Load bearing Structure*

In this system, walls are constructed using bricks/stone/block masonry and floor/roof slabs are of RCC/stone/composite or truss. It is cast in-situ system and called load bearing system as load of structure is transferred to foundation and then to ground through walls.



RCC Framed Structure

In this cast in-situ system, the skeleton of a structure is of RCC column and beam with RCC slab. The infill walls can be of bricks/blocks/stone /panels. The load of the structure is transferred through beam and column to the foundation.









Prevalent Construction Systems

Technology being Used

Load bearing Structure



RCC Framed Structure



Precast Concrete Construction - 3D Volumetric



It is the modern method of building by which precast concrete structural modules like room, toilet, kitchen, bathroom, stairs etc. & any combination of these are cast monolithically in Plant or Casting yard in a controlled condition.

These Modules transported, erected & installed using cranes and are integrated together in the form of complete building unit.







Conventional Construction Systems

Slow **Maximum Use of Natural Resources Waste Generation Air/Land/Water Pollution** Labor Intensive **Prescriptive Design Unhealthy Indoor Quality Regular Maintenance Energy Intensive Cast-in-situ Poor Quality High GHG Emissions** Unsustainable

Alternate Construction Systems

Fast

Optimum use of Resources Minimum Waste Minimum Pollution Industrialized System Cost-effective Design Better health & Productivity Low Life Cycle Cost **Energy Efficient Factory Made Quality Products Low GHG Emissions Sustainable**









MAP SHOWING SIX DIFFERENT LHP LOCATIONS









Sustainable Buildings

- *** 30%-50% reduction in energy use**
- ***** 40% reduction in water use
- * 35% reduction in GHG emission
- * 75% reduction in waste









3D Precast Volumetric Construction

- Replacing cast in situ RCC structural frame with factory made structural components – 3D
- Customized factory-made volumetric construction i.e. the entire module (room)







LHP-RANCHI (Precast Concrete Construction System – 3D Volumetric)

Advantages

- Upto 90% of the building work including finishing is complete in plant/casting yard leading to significant reduction in construction & occupancy time
- The controlled factory environment brings resource optimization, improved quality, precision & finish
- The required concrete can be designed using industrial by-products such as Fly Ash, Ground granulated blast furnace slag (GGBS), Micro silica etc. resulting in improved workability & durability, while also conserving natural resources. In this project Ground granulated blast furnace slag & silica fume is proposed in concrete.
- With smooth surface it eliminates use of plaster
- The monolithic casting of walls & floor of a building module reduces the chances of leakage
- The system has minimal material wastage (saving in material cost), helps in keeping neat & clean construction site and dust free environment
- Use of optimum quantity of water through recycling
- Use of shuttering & scaffolding materials is minimal
- All weather construction & better site organization









Light House Project (LHP) at Chennai, Tamil Nadu

(Technology: Precast Concrete Construction System-Precast Components)



No. of Dwelling Units : 1152 Nos. (G+5) No. of Block / Tower : 12 Blocks Units in each Block / Tower : 96 Nos. 2









2D Precast Concrete Construction

- Replacing cast in situ RCC structural frame with factory made structural components – 2D planar elements
- Customized Factory-made beams, columns, wall panels, slab/floors, staircases etc.











Concrete components prefabricated in precast yard or site and installed in the building during construction









LHP-CHENNAI (Precast Concrete Construction System-Precast Components Assembled at Site)

Advantages

- Quality of construction is enhanced significantly due to pre-casting of components by using sophisticated moulds and machineries in factory like environment, assured curing, assured specified cover to reinforcement, proper compaction of concrete results in to dense and impermeable concrete etc. Thus lesser maintenance cost during lifetime of project.
- Inbuilt eco-friendly method of construction in terms of more off-site works in controlled factory like environment results in to significant reduction in wastage of water, natural resources, air pollution and noise pollution.
- Safety of workforce achieved automatically as most of the works are carried out at ground floor in factory like environment, which ultimately enhances the work efficiency and quality.
- Wooden shuttering material is completely avoided and wastage of other construction materials reduced significantly; which results in to conservation of scarce natural resources like soil, sand, aggregate, wood etc.
- Advance procurement of major construction materials, advance pre-casting of structural components and assured completion of work within stipulated completion period will save cost towards escalation & early returns on investments, thus Substantial cost benefit to the client.





Light House Project (LHP) at Agartala, Tripura

(Technology: Light Gauge Steel Structural System & Pre-Engineered Steel Structural System)



No. of Dwelling Units : 1000 Nos. (G+6) No. of Block / Tower : 7 Blocks Units in each Block / Tower : A(112), B(154), C(118), D(168), E(168), F(168) & G(112)





3









PRE-ENGINEERED STEEL STRUCTURAL SYSTEM

• Replacing cast in situ RCC structural frame with factory made steel (hot rolled) structural system





















LIGHT GAUGE STEEL STRUCTURAL SYSTEMS

 Replacing cast in situ RCC structural frame with factory made light gauge steel (cold rolled) structural system





LHP-AGARTALA (Light Gauge Steel Structural System & Pre-engineered Steel Structural System)

Advantages

- Due to light weight, significant reduction in design earthquake forces is achieved. Making it safer compared to other structures.
- Fully integrated computerised manufacturing of LGSF sections provide very high precision & accuracy.
- Speedier
- Structure being light, does not require heavy foundation
- Structural elements can be transported to any place including hilly areas/ remote places easily
- Structure can be shifted from one location to other with minimum wastage of materials.
- Steel used can be recycled multiple times
- The system is very useful for post disaster rehabilitation work.









Light House Project (LHP) at Indore, M.P.

(Technology: Prefabricated Sandwich Panel System & Pre-Engineered Steel Structural System)



No. of Dwelling Units : 1024 Nos. (S+8) No. of Block / Tower : 8 Blocks Units in each Block / Tower : 128 Nos.









PREFABRICATED SANDWICH PANEL SYSTEMS

- EPS Core Panel Systems
- Other Sandwich Panel Systems
 - Fibre cement board
 - MgO Board
 - AAC panels





















• Replacing brick and mortar walls with dry customized walls made in factory









LHP-INDORE (Prefabricated Sandwich Panel System)

Advantages

- The system is dry walling system, brings speed in construction, water conservation (no use of water for curing of walling components at site).
- The sandwich panels have light weight material as core material, which brings resource efficiency, better thermal insulation, acoustics & energy efficiency
- Being light in weight, results in lower dead load of building & foundation size.









Light House Project (LHP) at Lucknow, U.P.

(Technology: Stay in-place Formwork System & Pre-Engineered Steel Structural System)

No. of Dwelling Units : 1040 Nos. (S+13) No. of Block / Tower : 4 Blocks Units in each Block / Tower : A(494), B(130), C(208) & D(208)











 \triangleright



Modular Tunnel form



- Tunnel formwork is a mechanized system for cellular structures. It is based on two half shells which are placed together to form a room or cell. Several cells make an apartment. With tunnel forms, walls and slab are cast in a single day.
 - The formwork is set up for the day's pour in the morning. The reinforcement and services are positioned and concrete is poured in the afternoon. Once reinforcement is placed, concrete for walls and Slabs shall be poured in one single operation. The formwork is stripped the early morning and positioned for the subsequent phase.
- Here the walls and slabs are cast in a form of a tunnel leaving two sides open whereas in monolithic concrete construction the entire room is cast in a single pour..





















STAY-IN-PLACE FORMWORK SYSTEM

- Replacing cast-in-situ
 Formwork with factory made
 formwork systems
- It is sacrificial formwork or lost formwork means formwork is left in the structural system to later act as insulation or reinforcement cage













Stay-In-Place PVC Wall Forms



- This is a prefinished wall formwork from M/s Novel Assembler Pvt. Ltd. comprising of rigid Poly-Vinyl Chloride (PVC) based polymer components that serve as a permanent stay-in-place durable finished form-work for concrete walls.
 - The extruded components slide and interlock together to create continuous formwork with the two faces of the wall connected together by continuous web members forming hollow rectangular components. The web members are punched with oval-shaped cores to allow easy flow of the poured concrete between the components.
- The hollow Novel Wall components are erected and filled with concrete, in situ, to provide a monolithic concrete wall.





LHP-LUCKNOW (Stay in Place PVC formwork System)

Advantages

- Having formwork already as part of system, the construction of building is faster as compared to conventional buildings. The formwork needs some support only for alignment purpose.
- The formwork consists of rigid PVC components, which do not corrode, chip or stain & resistant to UV, bacteria, fungi etc., thus ensuring long life of the structure.
- The polymer content used in manufacturing of formwork is up to 55% recycled content and are further recyclable, making it an eco-friendly material.
- The form work system has specific advantage for use in coastal areas as due to polymer encasement it offers higher durability.
- With concrete as filling material, the curing requirement of concrete is significantly reduced, thus saving in precious water resources.
- The formwork system does not have plastering requirement & gives a aesthetic finished surface in different color options.
- The system provides advantages in terms of structural strength, durability enhancement, weather resistance, flexural strength, thermal insulation and ease of construction.









Light House Project (LHP) at Rajkot, Gujarat

(Technology: Monolithic Concrete Construction System)











Rising EPS (Beads) Cement Panels



- Rising EPS (Beads) Cement Panels are patented panels from M/s Rising Japan Infra Pvt. Ltd. These are lightweight composite wall, floor and roof sandwich panels made of thin fibre cement/calcium silicate board as outer and inner faces with a core of EPS granule balls, adhesive, cement, sand, fly ash and other bonding materials in mortar form.
- The core material in slurry state is pushed under pressure into pre-set moulds. Once set, it shall be moved for curing and ready for use with RCC or steel framed structure.
- These panels are presently manufactured by the firm in China and shortly a plant will be installed in India.








MONOLITHIC CONCRETE CONSTRUCTION

- Replacing cast-in-situ Formwork
 with factory made customized
 formwork systems
- Formwork material is Aluminium / composites / steel having 100 to 500 repetitions
- Assembly line construction i.e. placing the formwork, pouring the concrete, moving the formwork to upper level







LHP-RAJKOT (Monolithic Concrete Construction using Tunnel Formwork)

Advantages

- Facilitates rapid construction of multiple/ mass modular units (similar units)
- Results in durable structure with low maintenance requirement
- The precise finishing can be ensured with no plastering requirement
- The concrete can use industrial by-products such as Fly Ash, Ground granulated blast furnace slag (GGBFS), Micro silica etc. resulting in improved workability & durability, while also conserving natural resource
- Being Box type structure, highly suitable against horizontal forces (earthquake, cyclone etc.)
- The large number of modular units bring economy in construction.







Thank you











3D MODULAR PRECAST 3rd Generation in Construction Technology









Content

- 1) About Us
- 2) What is 3D Modular Precast?
- 3) Need for Modular Construction
- 4) Implementation
- 5) Technology Comparison
- 6) Combination with Conventional Construction
- 7) Modular Buildings History, Case Studies, Adoption
- 8) Implementation in India
- 9) Key Notes





Vision







 Magicrete was founded with the idea of introducing modern methods of construction to help people make their homes better, faster & cheaper.

Journey So Far

 Introduced BLOX 10 years ago as a replacement of clay bricks. Transformed the walling industry with the product which was 10 times larger and made wall construction 5x faster.









Technology Road Map











Future Technology - 2020











Introducing 3rd gen in Construction Technology



- Lego like plug and play modules
- Cast and finished in factory
- Assembled on site
- 90% work done in factory

magicrete











Need for Modular Construction



Figure 1 (Source: Chapman and Butry, "Measuring and Improving the Productivity of the U.S. Construction Industry: Issues, Challenges, and Opportunities." Building and Fire Research Laboratory, National Institute of Standards and Technology: Gaithersburg, MD, 2008.

- Construction industry lags in Labour Productivity
- Need more Industrialization
- Enhanced Factory based approach like automobiles
- Prefab/ Modular Construction is the solution to fill this Gap.









Classification of Industrialized Construction





















shaping your concrete







Modularization of Floor Plan

- Identify the areas to be Modularized
- Make combination of 3D and 2D elements
- Optimize Structural stability, Productivity & Resource Efficiency











Classification of Modules



Walls + Roof + Floor

- Pros Highest Productivity & Resource Efficiency
- Cons Higher weight, 100% Mechanized Mold assembly required



Walls + Roof

- **Pros** Higher Productivity & Resource Efficiency
- **Cons** Higher weight, 100% Mechanized Mold assembly required

Walls + Floor

- **Pros** Higher Productivity & Resource Efficiency
- **Cons** Higher weight, 100% Mechanized Mold assembly required









Production Line











Finishing Line













Transport & Installation



Source: Google images







Transport & Installation











Dimproversity of Security of

shaping your concrete

Earthquake Resistant Design

 Specially designed inter-pod connections suitable for high seismic zones











Technology Comparison					
Parameter	MagicPod Conventional Const (3D Modular Precast)				
Resource Efficiency	Excellent (up to 60% less manpower)	ower) Poor			
Time Reduction	50% lesser	-			
Cost Reduction	0.85 x	1.00 x			
Safety	Low risk to manpower (only 10% of work on site)	High Risk of injury to manpower			
Sustainability	High (uses less & recyclable materials)	Low			
Functionality Parameters					
Thermal performance	Provides for use of light weight concrete /polystyrene infill	Normal			
Seismic Stability	High (suitable upto zone 4)	Medium			
Acoustic	>45dB sound reduction for 100mm wall	>40-45dB average sound reduction			
Water Tightness	High due to lesser joints	Depends on workmanship			
4		NUMBER OF DOD			













Technology Comparison

Factors	MagicPod (3D Precast Modular)	Light Gauge Steel Modular	2D Precast	Reinforced EPS Wall Panel	Monolithic Concrete Const.
%age Industrialization	90%	60 - 90%	30%	10%	0%
Durability	High	Medium	High	Medium	High
Life Cycle Cost	Low	High	Medium	Medium	Low
Strength	High	Low	High	Medium	Medium
Automation Possibility	High	Low	Medium	Low	Low
Finishing @ Plant	100%	60 - 80%	0%	0%	0%
Weight of Modules	High	Less	Less	Less	Less
MEP	Concealed	Exposed/Concealed	Concealed	Concealed	Concealed
Scalability	Very high	Low	Medium	Low	Medium
Speed of Exec.	Very high	High	Medium	Low	Medium
Mandays for 300 Sq. Ft. Work	12	22	18	34	31
magicrete	60% less man	power			









How can conventional building benefit from Modular Construction?

By Using Bathroom Pods



Bathroom is a repeatable component – hence can be modularized.



Involves all trades – RCC, Waterproofing, Tiling, Plumbing, Joinery in a cramped place of 50-100 sft, hence a critical job in project completion. Should be done offsite in parallel to building super structure construction.



Fixed Cost - no cost overruns.



Quality – can be easily controlled in a factory environment rather than on site.

Ready to use – fully finished bathrooms ready to use post installation.

Manhour density is highest in bathrooms. Hence ideal for modularization





shaping your concrete







Types of PBUs



Normal Concrete Pod





Lightweight Concrete Pod

Drywall Pod

Reasons for Adopting Bathroom Pods:

13 trades are done offsite, 40 % manpower reduction, 20% faster construction









Normal Concrete PBUs

1

MATERIALS AND STRUCTURE

- A monolithic casting
- Floor/wall made of concrete. Weight is about 5T to 6T
- Service pipes are either cast in or installed in recesses provided on walls
- Usually installed by critical path method as the POD is too heavy to be pushed in from the side of the building













Light Weight Concrete PBUs

MATERIALS AND STRUCTURE

- Floor/wall made of light weight concrete
- Wall thickness is 50mm, maximum weight including finishes is 3.5 tonnes
- Recess provided on walls to conceal service pipes
- Can be installed by critical path & noncritical path method











Dry Wall PBUs

MATERIALS AND STRUCTURE

- Concrete floor pod with drywall, weight is about 3T
- Steel sections as wall frame to secure drywall panels
- · Water pipes are concealed in the dry wall
- Backing plates on the wall to mount the fittings and accessories
- Non-critical path installation















Installation Methods







Drop in Critical Path

magicrete

Slide in Non Critical Path



shaping your concrete







Modular Buildings - History





Methodology:

G + 3 floors: Cast in Situ Elevator Core : Slip form Rooms: Modular Units Total Floors: 21 Total Rooms: 496 Installation: 46 Days

The Hilton Palacio del Rio Hotel, the first Concrete high rise Modular buildings in the world.

Timeline: 202 working days Location: Texas, 1968











Modular Buildings - History



Habitat 67, Built in 1967 in Montreal, Qubec, Canada. Habitat 67 comprises 354 identical, prefabricated concrete Modules arranged in various combinations, reaching up to 12 stories in height.









Modular Buildings - Case Study



The Modules, Philadelphia, US, 2010. Timeline: 9 Months Area: 80,000 Sqft. Total Floors : 5 Rooms: Modular Units Total Rooms: 89



Victoria Hall, Wembley, UK, 2011. Timeline: 16 months Total Floors: 19 Rooms: Modular Units Total Rooms: 435









Modular Buildings - Case Study











Modular Buildings - Case Study



SOHO Towers, Darwin Australia. 29 story high. The modules were completed & Finished in Ningbo, China & shipped to Darwin, Australia.











Technology Adoption













Implementation in India



Client: MOHUA - GOI Technology: 3D Modular Precast Timeline: 15 Months

Total Units: 1008 Apartments Unit Type: 1 BHK House for EWS Total Buildings: 7 x G+8









Key Notes

- The Big Change in Construction is coming...
- Onus lies with us...
- We as industry Participants & Drivers have the responsibility to Develop and Inculcate the technology and mainstream it...
- Govt. Institutions will play a very important role in developing Standards and Codes...
- Education Institutes shall also join hands & start courses to help Mainstreaming these technologies...